


# Since 1992



RETROFITTING & RENOVATION
WORKS AT HOUSE OF HABIB
CONTRACTOR:

RE-BUILD CONSTRUCTION PVT. LTD

- > Resides at mountain tip of Muhammad Ali Society, Karachi.
- ➤ Since early 90s, renovation work is going on by our hands not just architecturally but structurally.
- > Due to movement of mountain it is common to have marble damage landscaping repairing work.
- ➤ RBC is continuously maintaining the flooring, walls, underground and overhand tanks, boundary walls.
- ➤ Fiber lining technique is used by RBC for repair of existing Water Tanks.
- ➤ One of the renowned name in Pakistan in many endeavors, House of Habib is a satisfied client of RBC.







## UNILEVER HEAD OFFICE, AVARI TOWERS

RETROFITTING WORKS AT
UNILEVER HEAD OFFICE
CONTRACTOR:
RE-BUILD CONSTRUCTION PVT. LTD
CONSULTANT: MUSHTAQ & BILAL

- ➤ Specialized Seismic Retrofitting was required at Unilever Head Office so RBC presented the most efficient work plan.
- ➤ Initially around 30,000 holes were required in existing structure for jacketing work.
- ➤ For drilling holes Ferro scanning was done along with preparation of as-built drawings for installation of anchors.
- > Based on our drawings MS Plates were prepared.
- About 40,000 chemical rebars and 16,000 anchors of M12, M16 and M20 were fixed.
- ➤ All the work was executed efficiently. Jacketing by MS Plates installed using chemical anchors with high precision and without damaging existing structure internal reinforcement



## 2016

## DHA CITY PHASE 9



FIXING OF SOLAR PANELS IN HARD
STRATA
CONTRACTOR


CONTRACTOR:

RE-BUILD CONSTRUCTION PVT. LTD.
CONSULTANT: EA CONSULTANCY

- Solar panels were to be fixed by another contractor but during excavation rocky strata was found which made excavation very difficult job and the work could not be continued.
- Another approach was required for work execution so RBC provided the best work plan for execution of work which made the task easier and more efficient.
- ➤ Pull out tests were conducted and substrate was checked before drilling.
- > Design was based on the worst scenario considering minimum strength of substrate.
- Rebars were installed using Rawlplug® RKEX-II Epoxy in holes till 18" of depth.
- ➤ Then solar panels were fixed supported by pedestals. Hence the work was completed successfully.



## 




- ➤ Retrofitting was required at Metro generator view due to destruction caused by fire so RBC presented the most efficient work plan.
- Ferro scanning was done before drilling to avoid damage to internal reinforcement and to facilitate drilling of holes for anchors.
- > As-built drawings were also prepared.
- Slabs and beams were provided with MS Plates that were installed through chemical anchors. Lateral bracings were also fixed.
- > Anchors were placed in staggered pattern.
- > Jacketing of structural members was done efficiently.





## 2017



**TOWERS** 

**CONTRACTOR:** 


RE-BUILD CONSTRUCTION PVT. LTD

CONSULTANT: MUSHTAQ & BILAL

- > Specialized Seismic Retrofitting was required at Avari towers so RBC presented the most efficient work plan.
- > Complete structure analysis was conducted.
- ➤ Before drilling holes Ferro scanning was done along with preparation of as-built drawings for installation of anchors.
- > Based on our drawings MS Plates were prepared.
- MS Plates were installed using chemical anchors with high precision and without damaging existing structure internal reinforcement.
- About thousands of chemical rebars and anchors of M12, M16 and M20 were installed.
- > Pull out tests were conducted.
- > All the work was executed efficiently.







- ➤ Specialized Retrofitting was required at DHA Head Office so RBC presented the most coherent work plan.
- Schmidt hammer test was conducted to identify existing strength.
- Ferro scanning and As-built drawings were also prepared.
- > Pull out tests were also conducted.
- Excavation till bottom of footing was executed.
- Concrete was poured in foundations to increase their strength.
- Columns were Strengthen by Jacketing through MS Plates.
- MS Plates were installed through chemical anchors using high quality Epoxy.
- The Head Office was retrofitted and the whole task was executed efficiently.




# 2017

**CONTRACTOR:** 

RE-BUILD CONSTRUCTION PVT. LTD.


CONSULTANT: MUSHTAQ & BILAL



- > Retrofitting and renovation was required at Faraz Khan Bungalow.
- > Girders were fixed through anchors.
  These girders were later painted.
- All the irregular walls, beams and columns were flattened.
- > To control the cantilever action, steel sections were installed.
- Measures to control seepage and roof leakage were also taken.
- Layout of different rooms was reconfigured.
- All the necessary wiring, plumbing and ductwork was executed. After surface treatment the rooms were painted.







- Specialized Retrofitting was required at KIA Lucky Motors for two paint shops pits of 100m and 65m long.
- > These pit walls required internal distance of 5500mm but another contractor mistakenly constructed walls with lesser distance so we were approached for completing the task accurately.
- ➤ By using our retrofitting techniques we aligned walls and installed flushed SS Plates with countersunk mechanical anchors.
- Another requirement in the pit was regarding inclination slope of RCC Pit floor for proper flow of residual paint in Pit side by channel.
- We utilized our precise technique and experience, retrofit the walls and floor as per required slope in 100m and 65m length of floor.





- ➤ Specialized Retrofitting was required due to HVAC duct openings to avoid cantilever action.
- ➤ Openings of 1'x1' and 2'x2' were made, Channels of 6"x3"x3/8"were installed using anchor bolts of 10mm which were embedded up to 90mm.
- MS Plates of 8"x8"x3/8" were welded with channels and fixed using bolts of 10mm.
- Utilizing our expertise of retrofitting shear connectors of 10mm were installed at 12" c/c distance.
- New RCC beam of compressive strength of 3000psi was placed.
- Using our technical knowledge of retrofitting the Client needs were fulfilled and task was done accurately.
- ➤ Work was executed with taking every safety precaution because safety comes first for us.









SLAB JACKETING

CONTRACTOR:

RE-BUILD CONSTRUCTION PVT. LTD.

CONSULTANT: MUSHTAQ & BILAL

- ➤ Slab removal and jacketing work was required at KIA lucky motors.
- Drop panels were chiseled and fabrication of girders and plates was done.
- For Girders and plates were installed using Rawlplug® chemical anchors with Rawlplug® pure epoxy.
- For slab demolition, whole slab was vertically propped in grid pattern.
- > Through stitching cores pieces of slab were removed and later converted into debris.
- > Every challenge encountered was resolved by our experienced and qualified team utilizing experience of Retrofitting.





- ➤ Retrofitting by means of steel jacketing was required because the compressive strength for five columns at fifth floor were found less than required compressive strength.
- Ferro scanning was done along with preparation of as built drawings.
- ➤ MS Plates of 12mm thickness were fixed on column using Rawlplug® Stud anchors 16190-5.8 grade with high strength Rawlplug® RKEX-II Epoxy.
- > Over 500 anchors were installed.
- Corners of columns were welded via MS Angles. On top and bottom plates were fixed horizontally up to 2' by chemical anchoring and welded with vertical plate.
- > Using our retrofitting expertise, we were able to resolve every encountered challenge.





- ➤ Retrofitting was required due to extreme deterioration of beams so RBC presented the most efficient working plan.
- Chiseling of beam plaster and dismantling of wall portion was performed carefully.
- ➤ MS Channels were installed through Rawlplug® chemical anchors using Rawlplug® R-KEX-II Epoxy in drilled holes of dia 18mm up to depth of 5" on 12" c/c.
- ➤ MS plates of 6"x4"x3/8" were fixed.
- Concrete was laid properly then MS wire mesh was fixed on chiseled sections, 1" thick plaster was provided on slab and beams below installed MS Channels.
- Every complication encountered was overcome by using our technical knowledge of retrofitting.








- > To cater the additional load on crane beams strengthening was required so strengthening through CFRP was proposed as the best solution for this problem.
- The new required crane capacity was 140 tons and 180 tons.
- Designing was done by Aegion Fyfe Asia Pte Ltd for TYFO® Fibrwrap® System using codes ACI 318M-05 and ACI 440.2R-17.
- For CR-BM1 one vertical layer of TYFO® Fibrwrap® Carbon System on both sides of the beam was suggested along with 10mm thick steel plate at bottom by means of anchors at particular spacing.






- For CR-BM2 two different types of TYFO® Fibrwrap® Carbon System were recommended, first for the U-wrap of one layer whereas two layers of sagging wrap to be provided.
- Crane girders were designed and checked accurately under shear, flexure and torsion.

  Adequacy was section was checked.
- Columns were checked under loading and column analysis report was also provided.
- Software results and drawings were attached in technical report.
- Proper statement for the application of the Tyfo® Fibrwrap® Carbon systems was mentioned.









CFRP RETROFITTING FOR SEISMIC
STABILITY
CONTRACTOR:
RE-BUILD CONSTRUCTION PVT. LTD.


- The owner of the building intended to know about the structural stability of the building for future Seismic Activity and Wind loads.
- After performing structural testing it was concluded that building needs retrofitting because there were no Plinth beams and SOG.
- he slab thickness used in the building is too thin i.e. inadequate for such span and therefore as expected cracks were visible in the slab.
- > Structure was found vulnerable in case of future seismic activity.





- FRP Retrofitting was suggested for beams and columns as the most economical and efficient solution since it was demanded that operations won't be stopped even during retrofitting works.
- Designing was done by Aegion Fyfe Asia Pte Ltd for TYFO® Fibrwrap® System using codes ACI 318M-05 and ACI 440.2R-17.
- ➤ CFRP vertical wraps for columns and for inverted beams to control hogging were elaborated in drawings.
- > Proper statement for the application of the Tyfo® Fibrwrap® Carbon systems was shared.











**COLUMN** 

**CONTRACTOR:** 

RE-BUILD CONSTRUCTION PVT. LTD.

- ➤ InDatari's castle few columns of Ground floor were deteriorated due to rainwater so RBC was approached for solution.
- Column strengthening through CFRP was proposed as the best solution.
- ➤ Designing was done by Aegion Fyfe Asia Pte Ltd for TYFO® Fibrwrap® System using codes ACI M318-05 and ACI 440.2R.
- > PM interaction analysis were performed.
- First it was recommended to repair the deteriorated portion of column.
- ➤ It was suggested in design proposal to wrap CFRP horizontally and vertically extending 200mm above the deteriorated surface of





- column with one layer of Tyfo® Fibrwrap® Carbon System.
- > Proper lap length for horizontal layer was mentioned.
- ➤ By CFRP strength was increased up to 15.25 N/mm² from 11.72 N/mm² with just one layer (horizontal & vertical) following confined concrete model.
- ➤ Method statement for the application of the Tyfo® Fibrwrap® Carbon Systems was attached.
- Project briefs of similar cases were attached in technical proposal.







- ➤ Rehabilitation of splash zone of Hollow core reinforced concrete Jetty piles was required due to spalling of concrete and corrosion of rebars.
- The Tyfo® Fibrwrap® System (GFRP) was suggested to use to prevent further corrosion while compensating for loss of tensile force due to corroded rebars.
- Designing was done by Aegion Fyfe Asia Pte Ltd for TYFO® Fibrwrap® System using code ACI 440.2R-17.
- ➤ Designing was based on two assumptions: 1. 60% main (vertical) rebar area is lost due to corrosion.





- 2. 100% of spiral rebar area is lost due to corrosion.
- ➤ It was recommended to install one layer of Tyfo® Fibrwrap® System in vertical direction.
- For horizontal direction two layers of Tyfo® Fibrwrap® System were to be installed.
- Earlier there was no cathodic protection on structure so Tyfo® Fibrwrap® System was provided as a corrosion protection layer.
- Method statement for the application of the Tyfo® Fibrwrap® systems for Piles was attached with pictorial description of application method for proper guidance.
- > Similar completed international projects' reports were also attached.









CFRP RETROFITTING AT HONDA
CONTRACTOR:
RE-BUILD CONSTRUCTION PVT. LTD.

- Corbel strengthening was required due to missing steel links so RBC was approached for solution.
- Corbel strengthening through CFRP was proposed as the best solution for this problem.
- Designing was done by Aegion Fyfe Asia Pte Ltd for TYFO® Fibrwrap® System.
- ➤ It was suggested in design proposal to wrap the entire surface of cross-sectional area of missing links with three layers of Tyfo® Fibrwrap® Carbon System.
- > Proper method statement for the application of the Tyfo® Fibrwrap® Carbon Systems was attached.









- ➤ Specialized Retrofitting was required because boundary wall which was resisting soil at the back face, due to excessive load large cracks appeared which made wall incapable of bearing more load.
- ➤ MS Plates of 3" width with thickness of 1/4" at 12" c/c distance to be installed by means of anchors.
- ➤ Installation of ten Columns of W-Section 6"x6" and 8"X8" along with beams of WSection 6"x6" and 4"x4", bolting of anchors and welding of frame was done appropriately.
- ➤ Utilizing our expertise of retrofitting, activity was done accurately and client was satisfied.
- Work was executed with following all safety precautions because safety is our priority.






- At Aero Iconic Tower Shear Strengthening of Raft foundation was required so RBC presented the most efficient work plan
- ➤ Before drilling holes Ferro scanning was done along with preparation of as-built drawings for installation of anchors.
- After drilling on raft, MS Plates were fabricated and installed using Rawlplug® Mechanical anchors.
- Rawlplug® Mechanical anchors were torqued properly.
- For concrete jacketing of columns rebar doweling was also done using the Rawlplug® Pure Epoxy.
- > All the work was executed efficiently, adhering to safety precautions.







RETROFITTING ALZOHRA TOWER

CONTRACTOR:

RE-BUILD CONSTRUCTION PVT. LTD.

CONSULTANT: MUSHTAQ & BILAL


- > Slab removal and jacketing work was required at Al-Zohra Tower to make opening for staircase and to transfer its load.
- > MS Channels and MS plates were fabricated.
- After chiseling beam for plates, holes were drilled for anchors in order to fix plates.
- > Plates were fixed using Rawlplug® chemical anchors.
- Finally all Channels were fixed and welded.
- Slab was demolished in pieces using anti-vibration tool.
- Removed slab piece was shifted downward using chain pulley arrangement.
- Each piece was divided into small pieces to make debris.
- > The whole task was completed timely and efficiently.







# EDHI VILLAGE INTERCHANGE (M9)



**CFRP RETROFITTING** 

MAIN CONTRACTOR: FWO

**CONTRACTOR:** 

RE-BUILD CONSTRUCTION PVT. LTD.

- Due to the vehicular impact PC Girders were damaged and strengthening was required.
- > Girder strengthening through CFRP was proposed as the best solution for this problem.
- Designing was done by Aegion Fyfe Asia Pte Ltd for TYFO® Fibrwrap® System using codes ACI 318M-05 and ACI 440.2R-17.
- ➤ Five members of PC Girders were affected by the vehicular impact.
- ➤ One Girder (PCG1) was severely damaged whereas remaining four Girders (PCG2) were minimally damaged.






- ➤ In PCG1 10% of yield stress of tendons was lost and two bottom rebars and three stirrups were damaged.
- ➤ In PCG2 two rebars and one stirrup was damaged but tendons remained unaffected and intact.
- ➤ It was suggested in design proposal for Moment strengthening to use five layers of CFRP for PCG1 and two layers for PCG2.
- ➤ In case of Shear strengthening two layers of CFRP in PCG1 and one layer in PCG2 was suggested.
- ➤ Proper statement for the application of the Tyfo® Fibrwrap® Carbon systems on dry surfaces was mentioned.







- At Ideas the concrete started to spall off due to seepage and reinforcement was corroded so RBC was approached for specialized retrofitting.
- Anti-corrosive epoxy was coated on exposed reinforcement after replacement of damaged plaster with strengthening plaster made of different admixtures and hardener.
- ➤ MS Plates were installed at particular center to center spacing using Rawlplug® chemical anchors with Rawlplug® R-KEX-II Epoxy on drop panels.
- MS Channels were installed through Rawlplug® chemical anchors using Rawlplug® R-KEX-II Epoxy.
- > Every hindrance was overcome by using our technical knowledge of retrofitting.







CFRP RETROFITTING RCC SLAB
CONTRACTOR
RE-BUILD CONSTRUCTION PVT. LTD.

- ➤ At Indus Hospital Consultant wanted some openings in RCC Flat Slab therefore strengthening was required around opening.
- > Total four openings required strengthening.
- > RBC suggested CFRP wrap around openings was proposed as the best strengthening solution.
- Two openings were of size 2500mmx1000mm.
- > Third opening had size of 2250x1000.
- > Fourth opening had size of 1800x1000.
- ➤ Designing was done by Aegion Fyfe Asia Pte Ltd for TYFO® Fibrwrap® System using codes ACI M318-05 and ACI 440.2R.



- Around all four openings it was recommended to wrap two layers of 300mm Strip width & two layers of 400mm strip along both directions.
- Two layers of diagonal strips of 200mm was suggested.
- Method statement for the application of the Tyfo® Fibrwrap® Carbon Systems was attached.
- Project briefs of similar cases were attached in technical proposal.





BEAM
CONTRACTOR:
RE-BUILD CONSTRUCTION PVT. LTD.

- > To cater for the shortfall in design capacity causing cracks in some of the crane beams strengthening was required so CFRP was proposed as the best solution for this problem.
- ➤ Designing was done by Aegion Fyfe Asia Pte Ltd for TYFO® Fibrwrap® System using codes ACI 318M-05 and ACI 440.2R-17. Different load scenarios were considered in Analysis.
- ➤ One layer of TYFO® Fibrwrap® Carbon System as U-wrap in whole span to be provided.
- ➤ Proper statement for the application of the Tyfo<sup>®</sup> Fibrwrap<sup>®</sup> Carbon systems was mentioned.







FRP RETROFITTING OF ROOF SLAB CONTRACTOR: RE-BUILD CONSTRUCTION PVT. LTD.

- The beams were to be strengthened due to the reduction area of the steel reinforcement caused by corrosion so Tyfo® Fibrwrap® Systems was proposed to strengthen beams and slabs to achieve their original capacity before corrosion.
- ➤ Designing was done by Aegion Fyfe Asia Pte Ltd for TYFO® Fibrwrap® System using codes ACI 318M-05 and ACI 440.2R-17.
- The loss in area of the reinforcement is taken as 10% reduction in the diameter of the steel reinforcement.
- ➤ One layer of particular width of TYFO®
  Fibrwrap® Carbon System to be applied in






- x-axis and y-axis on Slab at specified center to center spacing.
- ➤ One layer of TYFO® Fibrwrap® Carbon System to be installed on beams for controlling hogging, sagging & shear at particular length & spacing.
- > Technical datasheet of products was provided.
- Software results and drawings were attached in technical report.
- Proper statement for the application of the Tyfo® Fibrwrap® Carbon systems on structural members was mentioned.









COTTAGES

**CONTRACTOR:** 

**RE-BUILD CONSTRUCTION PVT. LTD** 

- At Kings Cottage it was required to do waterproofing of very large and irregular expansion joint so RBC was approached to perform this task.
- ➤ After removing screed, backer rod was inserted in expansion joint which is soft and pliable filler designed to partially fill concrete expansion joints.
- ➤ Polysulphide sealant was used to caulk backer rod and chemically resist water penetration.
- ➤ Then Plastogrip which is water proofing membrane was applied through torching.
- ➤ The waterproofing work was done following standard procedures by utilizing our expertise.
- ➤ Rebuild Construction is making all efforts to protect existing structures and to meet client's requirements.







- ➤ At Sadabahar Banquet it was required to demolish RCC Pardi Beam to extend office so RBC was approached to execute work.
- Removal of RCC Pardi was done in pieces via anti vibration tool through stitch coring.
- > Foundations for two MS Columns were laid.
- ➤ Fabrication of MS Columns and MS Girders of W4x8 was done.
- ➤ MS Columns were inserted and erection of MS Girder was done beneath the cutting edge of RCC Pardi Beam.
- Columns and Girder was painted with Red oxide paint.
- ➤ All the work was executed with efficiency & proficiency within specified short deadline, adhering to safety precautions.









A-88, Gulshan-e-Iqbal, Block# 1, Karachi, Pakistan

info@rbc.com.pk

info@rb

www.rbc.com.pk

